



Straight Forward Technology

🌐 sfpctv.com

☎ 1300 707 765

☎ +61 3 9028 7388

✉ info@sfpctv.com

📍 2/15 Suffolk St Capel Sound 3940

🏢 Straight Forward Group Pty Ltd: ABN 78643385184.

Data Connectivity Repair - Portable Offices

Client

Not set

Location

Not specified

EXPIRED

Expired: 01/01/2026

Quote

Job Number

JN3782

Expiry: January 1, 2026

PDF created: 30/04/2026 5:03 AM

QUOTE SUMMARY

Testing and repair of data connections in portable office buildings following power surge. Includes replacing D10/D11 with dual outlets, UPS battery replacement, and rack cleanup.

LABOUR

\$1,280

MATERIALS

\$341

OPTIONAL EXTRAS

\$0

TOTAL

\$1,621



Straight Forward Technology

🌐 sfpctv.com

☎ 1300 707 765

☎ +61 3 9028 7388

✉ info@sfpctv.com

📍 2/15 Suffolk St Capel Sound 3940

🏢 Straight Forward Group Pty Ltd: ABN 78643385184.

ADDITIONAL INFORMATION

CUSTOMER DETAILS

Job Number: JN 3782 **Customer:** St Andrews Beach Brewery **Location:** 160 Sandy Road, Fingal VIC 3939

SUMMARY

This quote is to address **data connectivity issues** in the portable office buildings following a recent power surge. The portable offices were set up a few years ago and the data connections have not been serviced or tested since installation.

The printer has been an **ongoing issue** with its data connection. A previous workaround involved running a temporary ethernet cable to a different point, however this cable is currently on the floor and easily damaged. This quote includes replacing data points **D10 and D11** with dual outlets patched into the SABB Private VLAN, providing redundancy so staff can switch the wall-to-printer patch cord as a backup and troubleshooting procedure.

Work includes testing all data wall plates in both portable offices for **continuity and data transfer speeds** back to the comms hub. Any damaged cabling running under the buildings is to be repaired with waterproof joins where possible. The 19" rack is to receive a **compressed air blowout**, removal of redundant equipment, and both UPS units are to have their batteries replaced.

MATERIALS

- Contact cleaner and cleaning supplies
- Replacement UPS batteries (x2)
- Dual data outlets for D10/D11
- Patch cords
- Waterproof cable joiners (if required)

ASSUMPTIONS

- All faulty cabling can be joined and repaired with waterproof joiners
- Access to both portable offices and comms hub available during work
- Existing rack infrastructure is suitable for continued use after cleanup