# Straight Forward Technology

sfpctv.com
1300 707 765
+61 3 9028 7388
info@sfpctv.com
2/15 Suffolk St Capel Sound 3940
Straight Forward Group Pty Ltd: ABN 78643385184.


## Data Rack Cleanup & FTTP Coordination

Client
**Vanessa Santalucia**

Location
*Not specified*

EXPIRED
Expired: 29/12/2025

**Quote**

Job Number
**JN3768**

Expiry: December 29, 2025
PDF created: 23/11/2026 9:14 AM

## QUOTE SUMMARY

*Data rack tidy, UPS installation, remove Telstra router, add ventilation fans, review Foxtel, test racing SIM, and coordinate FTTP via Aussie Broadband.*

| LABOUR | MATERIALS | OPTIONAL EXTRAS | TOTAL |
|---|---|---|---|
| $0 | $0 | $0 | $0 |

Straight Forward Technology
sfpctv.com
1300 707 765
+61 3 9028 7388
info@sfpctv.com
2/15 Suffolk St Capel Sound 3940
Straight Forward Group Pty Ltd: ABN 78643385184.

## QUOTE DETAILS

This quote covers a comprehensive **data rack cleanup and network infrastructure upgrade** at the Berwick property.

### Data Rack Organisation

Complete reorganisation of the garage data rack including professional cable management, removal of redundant equipment, and proper labelling of all connections for future serviceability.

### Power Quality Solution

Installation of a **UPS with power conditioning** to address ongoing power quality issues. The unit is to be positioned in the rack below the current NVR location, providing clean power to all network equipment.

### Network Streamlining

Removal of the old Telstra router (currently daisy-chained from Starlink, retained only for IP addresses). This streamlines the network path for improved performance and reduces unnecessary points of failure.

### Thermal Management

Installation of cooling fans to the rack area to improve airflow and reduce heat buildup from networking equipment, extending equipment lifespan.

### Testing & Review

Test the hardwired ethernet connection to the racing simulator setup. Review Foxtel distribution requirements and confirm if the system is still needed or can be decommissioned.

### FTTP Coordination

Full management of Fibre to the Premises installation through Aussie Broadband. Straight Forward Technology handles the entire process including NBN liaison and meeting technicians onsite for installation.

## MATERIALS

- **UPS with Power Conditioning**– Line-interactive unit with AVR, sized for rack equipment load
- **Rack Cooling Fans**– Thermostat-controlled ventilation fans
- **Cable Management Kit**– Velcro ties, cable clips, rack-mount cable managers, and labelling system
- **Consumables**– Cable ties, patch leads as required

## ASSUMPTIONS

- Standard business hours work (no after-hours required)
- Single visit for rack tidy and UPS install; separate visit for FTTP coordination
- Customer to provide access to property for NBN technician visit
- Existing rack has sufficient space for UPS placement
- Shaun Mintoff (C-Bus) coordination via phone only unless site visit required

## ADDITIONAL INFORMATION

## CUSTOMER DETAILS

**Customer:** Vanessa Santalucia **Location:** 10 Elgin Street, Berwick VIC 3806

**Site Contact:** Shaun Mintoff (C-Bus) – 0419 870 006

## BEFORE WE START

- Customer to confirm if Foxtel distribution is still required or can be removed
- Confirm existing Aussie Broadband account details or advise if new account needed
- Shaun Mintoff (C-Bus) to be contacted regarding integration requirements

## QUESTIONS FOR YOU

Is the Foxtel distribution system still required, or can it be removed?Answer

Save Answer Delete Answer

Do you have an existing Aussie Broadband account, or shall we set one up?Answer

Save Answer Delete Answer